



ESTIMATE

Tidewater Home Improvement LLC
Class B Contractor #2705172863
414 Worster Ave
Hampton, Virginia 23669
United States

(757) 551-6413
tidehomepro.com

BILL TO

Nita Philip
Nita Philip
320 Atlantic Ave
Hampton, VA
United States

nitanatl@bellsouth.net

Estimate Number: 1418
Estimate Date: September 25, 2026
Valid Until: October 2, 2026

Grand Total (USD): \$6,530.42

1. Trench Guard System — 18 linear ft at the garage door: channel and grate set across the front of the garage opening to catch the water coming down the driveway and turn it away before it reaches the door.	18
2. Discharge Line — 179 linear ft around the back exterior wall of the garage: solid pipe carrying the collected water away from the house. Gravity fed.	179
3. Exterior French Drain — 26 linear ft: 4 in. perforated pipe in a cloth sleeve set in #57 gravel along the outside of the wall, graded to carry ground water away; two pop-up emitters at the ends of the run.	26
4. Discharge Pop-Ups — 2 ea: emitters at the ends of the lines so the water leaves the pipe at the surface and soaks away from the house.	2
5. Downspout Extensions — 2 ea: on the back exterior wall of the garage, taking roof water off the wall and into the discharge line.	2
6. General Conditions — mobilization, protection of the work area, material runs and daily clean-up through the project.	1
10% Customer Discount	1

Grand Total (USD): **\$6,530.42**

Notes / Terms

NOT INCLUDED: any crawlspace work — no vapor barrier, no encapsulation and no dehumidifier; no sump pump; no electrical work; no structural repair to the house; gutter work beyond the two downspout extensions listed; repair to driveway, concrete, paint or finish surfaces; any work not listed in the scope above.

Notes:

**Ground settles where it is disturbed — final grading and grass are the owner's to finish.

**Contractor is not responsible for damage caused inside the home while working on the exterior.



Warranty:

**12 months workmanship on the work performed; 12 months on the drainage system.

Payment Terms:

Total Project Cost: \$7,256.02

10% Customer Discount: -\$725.60

Total Project Cost: \$6,530.42

Deposit to Schedule: \$3,265.21

Final Payment: \$3,265.21

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Questions on this estimate: Jeff Wilson — text or call 757-322-7171

Validity: valid until October 2, 2026.



SCOPE OF WORK

1. Trench Guard System: install 18 LF of trench guard (channel and grate) across the front of the garage door to intercept the water coming down the driveway;
 2. Discharge Line: install 179 LF of discharge line around the back exterior wall of the garage, carrying the collected water away from the house;
 3. Exterior French Drain: install 26 LF of french drain — 4 in. perforated pipe in a cloth sleeve set in #57 gravel along the outside of the wall, graded away — with 2 pop-up emitters;
 4. Downspout Extensions: install 2 downspout extensions on the back exterior wall of the garage, taking roof water off the wall and into the discharge line;
 5. General Conditions: mobilization, protection of the work area, material runs and daily clean-up;
- 10% Customer Discount: -\$725.60

JOB DESCRIPTION

Water runs down the driveway and against the back exterior wall of the garage and gets in — at the garage door on one side and through the block rear wall on the other. This estimate takes that water away from the garage and the house: a trench guard across the garage opening, a discharge line around the back wall, a french drain along the wall with pop-up emitters, and two downspout extensions so the roof water leaves the wall. All of it is gravity fed — no pumps. No crawlspace work is included and nothing structural is being done.

Questions on this estimate: Jeff Wilson — text or call 757-322-7171

View your full scope of work online: <https://tidewater-est-320-atlantic.pages.dev/>